

Detailed Statement

Proposed Alterations at 1620 SE Waverly Dr.

11/7/2024

Prepared For: City of Milwaukie, Oregon

Prepared By: Fowler Home + Design

The summary of proposed alterations to the existing residence on the main floor include the addition of a primary wing located on the far east side of the residence that houses a bedroom, bath, and walk-in closet, the addition of a 306 s.f. prefabricated conservatory at the southwest side of the residence, extending the west garage wall 6', and extending the south kitchen and nook walls 8.5' and 6' respectively. The total main floor additions including the conservatory amounts to 1,436 s.f.

On the upper floor, slight wall extensions are made on the north wall above the porch, the east wall at the existing bath, the south wall, and west wall which amounts to a total of 348 s.f. additional area. The upper floor also includes the additions of a deck on the northwest and the south. All existing roofs are kept as existing as much as possible, such as the tallest roof form over the primary mass of the existing residence and the flat roof over the primary suite bath. The proposed roofs maintain the existing roof slopes and do not exceed the existing maximum height.

The two most critical elements outlined in the 1988 historic resource survey are the PERSON and STYLE categories. The STYLE category states the residence as Colonial Revival style with elements of interest centered primarily around the entrance of the residence such as the paneled doors, Swan's neck pediment, full entablature, and Ionic pilasters. Additional noted elements of interest include quoining at the entrance, an endwall chimney, a palladian window, the polygonal bay window with tent roof and spandrel, and the belt course over the second story windows.

The proposed alterations have little to no impact on the PERSON category as the overall character and layout of the existing residence is maintained. For the STYLE category, the key historic features are to remain and the proposed minor alterations add to the existing style such as the colonial wooden balusters.

The alterations will also create a more efficient and safe residence through better insulation, higher performance windows, and seismic fortification of the structure.

The proposed alterations adhere to all relevant zoning and development standards. Refer to the plans and elevations for further information.

Approval Criteria:

1. *Retention of Original Construction*

Distinguishing original qualities defining a resource's character shall not be destroyed. Removal or alteration of historic materials or distinctive architectural features should be avoided when possible.

Response: The majority of the existing walls and the primary and tallest portion of the roof will remain. The key design elements are to remain which includes the paneled doors, Swan's neck pediment, full entablature, Ionic pilasters, quoining at the entrance, an endwall chimney, a palladian window, the polygonal bay window with tent roof and spandrel, and the belt course over the second story windows. The criterion is met.

2. *Building Height*

Existing building heights should be maintained. Alteration of roof pitches shall be avoided. Raising or lowering a building's permanent elevation when constructing a foundation shall be avoided, except as required by building code or floodplain development permit.

Response: The tallest roof form will remain, thus maintaining the existing buildings highest elevation. All proposed roofs match the existing roof pitches. The flat roof of the existing east wing of the home, the pediments above windows on the west wing of the home, the flat roof above the two story bay window, and the pediment above the front entry will all be maintained. The criterion is met.

3. *Horizontal Additions*

The scale and proportion of building additions, including the relationship of windows to walls, shall be visually compatible with the traditional architectural character of the historic building. Contemporary design for alterations and additions is acceptable if the design respects the building's original design and is compatible with the original scale, materials, and window and door-opening proportions of the building.

Response: All proposed alterations, including the relationship of windows to walls, remain compatible with the original architectural character, scale, materials, and proportions of the historic residence. The criterion is met.

4. Windows

Window replacements shall match the visual qualities of original windows as closely as possible. Wood window frames are preferred in meeting this standard. However, if non wood replacements exhibit similar visual qualities as their wooden counterparts, they may be acceptable. The original number of window panes shall be maintained or restored when replacements are required.

Response: The window replacements will match the frames and grids of the original windows as closely as possible. The criterion is met.

5. Restoration Possible

Except where building code precludes it, new additions or alteration to buildings shall be done in such a manner that if such additions or alterations were to be removed in the future, the essential form and integrity of the original building could be restored.

Response: The proposed alterations and additions shall be constructed in such a manner that the additions and alterations could be removed and restored to its existing condition, thus preserving the essential form and integrity of the original building. The criterion is met.

6. Signs and Lighting

Signs, lighting, and other appurtenances (such as walls, fences, awnings, and landscaping) shall be visually compatible with the original character of the building.

Response: There is no proposed signage. The proposed lighting and other appurtenances will be visually compatible with the original character of the building. The criterion is met.

7. Time Period Consistency

Buildings shall be recognized as products of their own time. Alterations that have no Historical basis or which seek to create an earlier appearance shall be avoided.

Response: All proposed alterations and additions are deeply based in the Colonial Revival style. The criterion is met.

8. Visual Integrity/Style

Distinctive stylistic features, such as a line of columns, piers, spandrels, or other primary structural elements, or examples of skilled craftsmanship which characterize a building, shall be maintained or restored as far as is practicable.

Response: The distinctive stylistic features on the high preservation priority areas of the home are to be maintained. Any proposed features are of the Colonial Revival Style. The criterion is met.

9. Replacement or Additional Materials

Whenever possible, deteriorated architectural features shall be repaired rather than replaced. In the event replacement of an existing feature is necessary, or an addition is proposed, new materials should match those of the original building, to the extent possible, in composition, design, color texture, and other visual qualities.

Response: The proposed alterations and additions match the existing materials of the historic residence, such as stucco siding. The criterion is met.

10. Buffering

An appropriate buffer or screen, as provided under Subsection 19.504.6, may be required when a new commercial or industrial improvement or use is proposed on or adjacent to a designated resource, or within or adjacent to an historic district.

Response: Our current proposal does not include any buffering or screening. However, if required, the buffering or screening will be consistent with requirements from NPS. The criterion is not applicable.

1620 SE WAVERLY DRIVE MILWAUKEE, OR. 97222

- ALL EXCESS GRADING MATERIAL TO BE EXPORTED TO AN APPROVED DISPOSAL LOCATION.
- ALL AREAS UNDER GARAGE FLOORS, SIDEWALKS, DRIVEWAYS, ETC., TO BE COMPACTED GRANULAR FILL.
- THERE WILL BE A SLIGHT OVER EXCAVATION TO PROVIDE CONCRETE FORMING ALL AROUND NEW STRUCTURE.
- PROVIDE COUNTY/CITY APPROVED SEDIMENT FENCING AROUND EXCAVATED AREA PRIOR TO EXCAVATION AND CONSTRUCTION.
- PROVIDE COUNTY/CITY APPROVED STABILIZED GRAVELED CONSTRUCTION ENTRANCE PRIOR TO EXCAVATION AND CONSTRUCTION.
- STOCKPILES MUST BE COVERED WITH MULCH OR PLASTIC SHEETING BETWEEN OCTOBER AND APRIL.
- CONTRACTOR/ SUB-CONTRACTOR TO VERIFY LOCATION OF ALL UTILITIES PRIOR TO EXCAVATION.
- BOUNDARY AND TOPOGRAPHY INFORMATION HAS BEEN PROVIDED TO FOWLER HOME DESIGN INC. FOR THE USE OF THE CONTRACTOR. IT IS THE CONTRACTOR'S RESPONSIBILITY TO VERIFY THE ACCURACY OF THIS INFORMATION. IT IS THE SOLE RESPONSIBILITY OF THE CONTRACTOR OWNER TO VERIFY ALL SITE CONDITIONS INCLUDING FILL PLACED ON SITE.
- ELEVATION LEGEND:
 EE = EXISTING GRADE ELEVATION
 FF = FLOOR ELEVATION
 PE = FINISHED FLOOR ELEVATION
- PROVIDE A MINIMUM GRAVEL BASE UNDER ALL DRIVEWAY AREAS.
- PROVIDE A 4' MINIMUM GRAVEL BASE UNDER ALL SIDEWALK AND PATIO AREAS.
- PIPE ALL STORM DRAINAGE FROM THE BUILDING TO A COUNTY/CITY DISPOSAL POINT/CONNECTION.
- MAXIMUM SLOPE OF CUTS AND FILLS TO BE TWO (2) HORIZONTAL TO ONE (1) VERTICAL FOR BUILDINGS, STRUCTURES, FOUNDATIONS, AND RETAINING WALLS.
- PROVIDE AND MAINTAIN FINISH GRADE WITH POSITIVE DRAINAGE AWAY FROM STRUCTURE ON ALL SIDES WITH A SLOPE OF 6% MINIMUM IN 10'-0".


EROSION CONTROL PLAN

- COVERED STOCKPILES - COVER W/ PLASTIC OCT. 1 - MAY 31.
 SEDIMENT FENCE
 CONSTRUCTION ENTRANCE (ACCESS POINT)
 WORK STAGING/ MATERIAL STORAGE
N.B.
 3' APPROVED COVER ON ALL AREAS OF BARE GROUND UNTIL PERMANENT LANDSCAPE IS IN PLACE
 NON-WOVEN INLET PROTECTION AT THE FIRST DOWNSTREAM CATCH BASIN
 WOODEN CURB RAMP
 DIRECTION OF STORM-WATER FLOW ON SITE
 NO STOCKPILES ARE TO BE LOCATED IN THE SIDE SETBACK AREAS.



IMPORTANT DISCLOSURE
 PLEASE READ:
 THE PLANS YOU ARE PURCHASED ARE FOR THE CONSTRUCTION OF ONE HOME ONLY.
 PLANS ARE CIRCUMSCRIBED BY THE PROPERTY LINE AND ARE NOT TO BE USED OUTSIDE OF THE PROPERTY LINE.
 THESE PLANS ARE COPIRIGHTED AND IT IS A VIOLATION OF FEDERAL LAW TO COPY THESE PLANS.
 FOWLER HOME DESIGN LLC WILL NOT PROSECUTE ANY CONTRACTOR WHO COPIES THESE PLANS.
 FURTHERMORE IT IS UNDERSTOOD THAT IT IS COMPLETELY THE RESPONSIBILITY OF THE CONTRACTOR TO MAKE SURE THAT THE HOME DESCRIBED HEREIN ON ANY PARTICULAR SITE MEETS ALL LOCAL CODES AND REGULATIONS.
 FOWLER HOME DESIGN LLC TAKES NO RESPONSIBILITY FOR THE COMPLIANCE OF THIS PLAN TO ANY CODE OR ANY BUILDING SITE.

**CONTRACTOR TO
VERIFY EXISTING
CONDITIONS AND
UTILITIES, TYP.**



ELEVATION NOTES:

- ROOFING MATERIAL TO BE ARCHITECTURAL COMPOSITION MATERIALS AND 5" STANDING SEAM METAL ROOFING SEE ELEVATION PAGE. ROOF SHINGLES TO BE NAILED PER MANUFACTURED INSTRUCTIONS FOR 80 MPH MINIMUM WIND AREAS.
- ROOF PITCH TO BE SHOWN ON PLANS.
- ALL EAVES TO BE NOTED ON PLANS WITH A 5" GALVANIZED FACIA GUTTER ON SPECIFIED FACIA BD.
- PROVIDE 3" GALVANIZED DOWNSPOUTS (DS) AS SHOWN ON ROOF FRAMING PLAN.
- SIDING NOTED ON PLANS.
- ALL WINDOW & DOOR TRIM TO BE 5/4 X 4 AT SIDES AND 5/4 X 6 CROWN & SILL.
- SIDING TO BE SPECIFIED ON PLAN. CAULK ALL CORNER BOARDS, JOINTS, WINDOWS, DOORS AND SURROUNDS.
- ALL CORNER BOARD TRIM TO BE 2 X 4 PRIMED BD. AS SHOWN ON PLAN.
- COVERED PORCHES AND EAVE SOFFITS TO BE 1/2" EXT. FLYWOOD OR EQUAL TOO. CAULK ALL JOINTS.
- MASONRY VENEER TO BE CULTURED STONE OR EQUAL AS SHOWN ON PLAN. PROVIDE GALVANIZED FLASHING ON A MASONRY SILL CAP OVER VENEER. VERIFY LOCATION AND TYPE OF MASONRY WITH BUILDER PRIOR TO CONSTRUCTION.
- PROVIDE 2 X 10 ROUGH SAWN CEDAR OR EQUAL AT ALL BELLY BANDS WITH A GALVANIZED "Z" FLASHING AT EXPOSED TOP. LOCATIONS ARE SHOWN ON PLAN UNLESS OTHERWISE NOTED.
- PROVIDE VENTS AS SHOWN. SHUTTERS AND TRIM ON ELEVATIONS AS SHOWN ON PLAN.
- PROVIDE VINYL WINDOWS AS SHOWN ON PLAN.
- EXPOSED CONCRETE WALKS TO BE BROOCHED FINISH AS SHOWN ON PLAN.
- MAXIMUM FOUNDATION EXPOSURE TO BE 18' FROM FINISHED GRADE.
- MAXIMUM SLOPE OF CUTS AND FILLS TO BE TWO (2) HORIZONTAL TO ONE (1) VERTICAL FOR BUILDINGS, STRUCTURES, FOUNDATIONS, AND RETAINING WALLS.
- FINISH GRADE TO BE 18" MAXIMUM SLOPE WITH A 6" MINIMUM IN 10'-0" MINIMUM SLOPE AWAY FROM STRUCTURE ALL AROUND.
- SEE ELEVATIONS FOR ANY ADDITIONAL NOTATIONS THAT MAY BE OF IMPORTANCE.
- ALL WORK IS TO COMPLY WITH THE LATEST ADOPTED VERSIONS OF THE INTERNATIONAL ONE & TWO FAMILY DWELLING CODE, UIFORM BUILDING CODE OF ANY APPLICABLE STATE, COUNTY OR LOCAL JURISDICTION.
- PRIOR TO BEGINNING CONSTRUCTION, THE PLANS AND SPECIFICATIONS SHALL BE APPROVED BY THE LOCAL BUILDING AUTHORITY.
- THE CONTRACTOR IS RESPONSIBLE TO CHECK THE PLANS AND NOTES TO DETERMINE WHETHER ANY ENHANCEMENTS OR CHANGES ARE NEEDED. START ANNOTATIONS CONSTRUCTION, THE DESIGNER IS NOT RESPONSIBLE FOR CONSTRUCTION MEANS AND METHODS ACTS OR OMISSIONS OF THE CONTRACTOR AND/OR SUBCONTRACTOR.
- BUILDING THIS PLAN ON SITE CONDITIONS DIFFERENT FROM THOSE SHOWN ON THE PLANS MAY REQUIRE MODIFIED FOUNDATION AND FRAMING DETAILS. THE CONTRACTOR IS RESPONSIBLE TO REVIEW SPECIFIC SITE CONDITIONS WITH THE DESIGNER BEFORE CONSTRUCTION.
- VERIFY FOUNDATION AND FRAMING DETAILS (WHERE APPLICABLE) WITH MECH. PLUMBING, ELECTRICAL OR OTHER SUBCONTRACTORS TO ASSURE PROPER CONSTRUCTION INSTALLATION.
- PLUMBING, ELECTRICAL AND MECHANICAL DIAGRAMS, LAYOUTS AND/OR DESIGN TO BE SUPPLIED BY CONTRACTOR AND/OR SUB-CONTRACTOR.
- ENGINEERED PRODUCTS (ROOF TRUSSES, FLOOR JOISTS) TO HAVE DESIGN, ENGINEERING SPECIFICATIONS AND LAYOUT SUPPLIED FROM MANUFACTURER.
- WRITTEN DIMENSIONS SHALL HAVE PRECEDENCE OVER SCALED DIMENSIONS. DO NOT SCALE THE DRAWINGS. THE CONTRACTOR SHALL VERIFY AND IS RESPONSIBLE FOR ALL DIMENSIONS (INCLUDING ROUGH OPENINGS) AND CONDITIONS ON THE JOB.
- SPECIFIC MANUFACTURERS AND MATERIALS DEPICTED ON THESE PLANS ARE AN INDICATION OF QUALITY AND STRENGTH. VERIFY ALL CONSTRUCTION MATERIAL SUBSTITUTION WITH CURRENT APPLICABLE BUILDING CODES AND LOCAL BUILDING OFFICIALS PRIOR TO INSTALLATION/SUBSTITUTION.
- CONTRACTOR SHALL BE RESPONSIBLE FOR ANY VARIATIONS OR DEVIATIONS FROM THE ORIGINAL PLANS WITHOUT WRITTEN CONFIRMATION FROM THE DESIGNER.
- ALL DIMENSIONS AND SQUARE FOOTAGE MAY VARY.
- THE TYPE OF EXTERIOR FINISH, THE INSTALLATION AND THE WATERPROOFING DETAILS ARE TO BE THE FULL RESPONSIBILITY OF THE OWNER/BUILDER. THIS DESIGNER ASSUMES NO RESPONSIBILITY OF THE BUILDING ENVELOPE.

DESIGN LOADS:

	100 MPH OR LESS
WIND	100 MPH OR LESS
SEISMIC DESIGN CATEGORY	D
DOOR	10 INCHES
ROOF DEAD LOAD	11 PSF
ROOF LIVE LOAD	20 PSF
ROOF SNOW LOAD	25 PSF
FLOOR DEAD LOAD	15 PSF
FLOOR LIVE LOAD	40 PSF
STAIRS	40 PSF
EXTERIOR BALCONIES	60 PSF
DECKS	60 PSF

IMPORTANT DISCLOSURE PLEASE READ:

THE PLANS YOU HAVE PURCHASED ARE FOR THE CONSTRUCTION ONE HOME ONLY. IT IS ILLEGAL TO BUILD FROM THESE PLANS MORE THAN ONCE WITHOUT THE WRITTEN PERMISSION OF THE DESIGNER. THESE PLANS ARE COPYRIGHTED AND IT IS A VIOLATION OF FEDERAL COPYRIGHT LAW TO REPRODUCE THESE PLANS WHOLLY OR PARTIALLY. IT IS ALSO A VIOLATION OF ANY VIOLATION OF ITS COPYRIGHTED DESIGN AND PLANS. THE CONTRACTOR IS RESPONSIBLE TO CONSTRUCT THE HOME DESCRIBED HEREIN IN ANY PARTICULAR SITE. THE DESIGNER IS NOT RESPONSIBLE FOR THE CONSTRUCTION OF THE HOME. THE DESIGNER, FOWLER HOME DESIGN LLC, TAKES NO RESPONSIBILITY FOR THE CONFORMANCE OF THIS PLAN TO ANY CODE OR ANY BUILDING SITE.




FRONT ELEVATION

5,236 SQ. FT. EXISTING RESIDENCE
1,784 SQ. FT. NEW ADDITION
7,020 SQ. FT. TOTAL

WINDOW SCHEDULE


MARK	SIZE & TYPE	QUANTITY
▲	NOT USED	-
▲	3-1/2"X6"X10" PX MULLED	1
▲	4-1/2"X6"X10" PX-CMT-X-CMT-PX	1
▲	2"X6"X10" CMT.	1
▲	2"X6"X10" CMT.	3
▲	3-1/2"X6"X10" PX MULLED	1
▲	2"X6"X10" CMT.	1
▲	3-1/2"X6"X10" PX MULLED	1
▲	2-1/2"X6"X10" CMT. MULLED	1
▲	2"X6"X10" CMT.	1
▲	2-1/2"X6"X10" CMT. MULLED	1
▲	2"X6"X10" CMT. MULLED	1
▲	3-1/2"X6"X10" PX MULLED	1
▲	2"X6"X10" CMT.	1
▲	4"X6"X10" PX	3
▲	4"X6"X10" PX MULLED	1

NOTES:
- ALL WINDOWS TO HAVE GRIDS UNLESS
- CONTRACTOR TO CONFIRM ALL WINDOW SIZES
AND QUANTITIES



EXIST. FRONT ELEVATION

5,236 SQ. FT. EXISTING RESIDENCE



EXIST. RIGHT SIDE ELEVATION

5,236 SQ. FT. EXISTING RESIDENCE



RIGHT SIDE ELEVATION

5,236 SQ. FT. EXISTING RESIDENCE
1,784 SQ. FT. NEW ADDITION
7,020 SQ. FT. TOTAL

CONTRACTOR TO SELECT 1 OPTION	
ORIG. 2021 TABLE N401/2	
1	HIGH EFFICIENCY HVAC SYSTEM GAS-FIRED RANGE OR BOILER WITH PRIMARY COP OF 9.4 GAS-FIRED RANGE OR BOILER WITH COP OF 10.0 TO 10.5 FOR COOLING OR GROUND SOURCE HEAT PUMP COP OF 3.5, OR ENERGY STAR RATED
2	HIGH EFFICIENCY WATER HEATING SYSTEM W/MIN. 0.950, OR ELECTRIC HEAT PUMP WATER HEATER W/MIN. 2.0 COP OR NATURAL GAS/PROPANE TANKLESS W/MIN. 0.950, OR ELECTRIC HEAT PUMP WATER HEATER W/MIN. 2.0 COP OR NATURAL GAS/PROPANE TANKLESS WATER HEAT RECOVERY UNIT INSTALLED ON MIN. OF ONE SHOWER SHAR
3	WALL INSULATION UPGRADE EXTERIOR WALLS U-0.048R-21 CONVENTIONAL FRAMING WITH R-3.0 CONTINUOUS INSULATION
4	ADVANCED ENVELOPE WINDOWS U-0.03, LABEL MEASURED AVERAGE) AND FLAT CEILINGS U-0.01R-0.60, AND FLOOR LOCATIONS U-0.02R-0.30, R-3.0 EDGE INSULATION TO R-3.0 CEILINGS IN FLOORS & R-3.0 FOR 30" OR R-3.0 FULLY INSULATED SLAB)
5	DUCTLESS HEAT PUMP FOR ZONING UNITS WITH ALL-ELECTRIC HEAT PROVISION ZONAL ELECTRIC HEAT SOURCES, AND PROGRAMMABLE THERMOSTAT FOR ALL HEATERS IN BEDROOMS
6	HIGH EFFICIENCY THERMAL ENVELOPE UA PROPOSED UA IS 6% LOWER THAN THE CODE UA
7	GLAZING AREA GLAZING AREA MEASURED AS THE TOTAL OF FRAMED OPENINGS IS LESS THAN 5% OF CONDITIONED FLOOR AREA
8	3-ACH AIR LEAKAGE CONTROL & EFFICIENT VENTILATION ACHIEVE A MAX. OF 3.0 ACH DUE TO THE VENTILATION SYSTEM AND THE EXISTING RESIDENCE HAS A SINGLE-HOUSE VENTILATION SYSTEM INCLUDING HEAT RECOVERY WITH A MINIMUM SENSIBLE HEAT RECOVERY EFFICIENCY OF NOT LESS THAN 66%


IMPORTANT DISCLOSURE
PLEASE READ.

THE PLANS YOU HAVE PURCHASED ARE FOR THE CONSTRUCTION OF THE HOUSE ONLY. UNDER NO CIRCUMSTANCES IS IT LEGAL TO BUILD PROPS, STAGING, OR ANY OTHER ITEMS WITHOUT THE WRITTEN CONSENT FROM THE DESIGNER TROY FOWLER. THESE PLANS ARE COPYRIGHTED AND IT IS A VIOLATION OF FEDERAL LAW TO COPY OR REPRODUCE THESE PLANS. FOWLER HOME DESIGN LLC WILL FULLY PROSECUTE ANY ACT OF INFRINGEMENT OF THESE PLANS. FOWLER HOME DESIGN LLC IS NOT RESPONSIBLE FOR THE CONSTRUCTION OF THE HOUSE. THE CONTRACTOR IS RESPONSIBLE FOR THE CONSTRUCTION OF THE HOUSE AND WITHIN THE CONFINES OF THE GOVERNING JURISDICTION THAT CONSTRUCTION IS THE CONTRACTOR'S RESPONSIBILITY. FOWLER HOME DESIGN LLC TAKES NO RESPONSIBILITY FOR THE CONFORMANCE OF THIS PLAN TO ANY CODE OR ANY BUILDING SITE.

WINDOW SCHEDULE

MARK	SIZE & TYPE	QUANTITY
△	NOT USED	-
△	3-2'6"x8'0" PX MULLED	1
△	4-2'0"x8'0" MULLED PX-C-SHT-C-SHT-PX	1
△	2'0"x4'0" CSHT.	1
△	2'0"x6'0" CSHT.	3
△	3-2'0"x8'0" MULLED PX-C-SHT-PX	1
△	2'0"x8'0" CSHT.	5
△	3-2'0"x8'0" MULLED PX-C-SHT-PX	1
△	2-2'0"x8'0" CSHT, MULLED	1
△	2'0"x8'0" CSHT.	1
△	2-2'0"x8'0" CSHT, MULLED	1
△	2'0"x8'0" PX	8
△	3-2'0"x3'4" MULLED PX-C-SHT-PX	1
△	2-2'0"x8'0" CSHT, MULLED	1
△	3-2'0"x8'0" MULLED PX-C-SHT-PX	1
△	4'0"x8'0" PX	3
△	4-2'0"x8'0" MULLED PX-C-SHT-C-SHT-PX	1

NOTES:
- ALL UNDOORS TO HAVE GRIDS UNO
- CONTRACTOR TO CONFIRM ALL WINDOW SIZES
AND QUANTITIES




EXIST. LEFT SIDE ELEVATION

5,236 SQ. FT. EXISTING RESIDENCE



REAR ELEVATION

5,236 SQ. FT. EXISTING RESIDENCE
1,784 SQ. FT. NEW ADDITION
7,020 SQ. FT. TOTAL






EXIST. REAR ELEVATION

5,236 SQ. FT. EXISTING RESIDENCE



LEFT SIDE ELEVATION

5,236 SQ. FT. EXISTING RESIDENCE
1,784 SQ. FT. NEW ADDITION
7,020 SQ. FT. TOTAL



**IMPORTANT DISCLOSURE
- PLEASE READ:**

The plans you have purchased are for the construction one home only. Under no circumstances is it legal to build prints or plans more than once without the written consent from the designer Troy Fowler. These plans are protected by the federal law of federal copyright laws to reproduce these plans or any portion of them in whole or in part, or to copy or translate them into another language, is illegal. Any violation of its copyrighted designs and plans, furthermore it is understood that it is completely the responsibility of the contractor to insure the home described herein, on any particular site and under all conditions of construction. Troy Fowler Home Design takes no responsibility for the conformance of this plan to any code or any building site.

WALL LEGEND	
	- NEW (N) WALL
	- EXISTING (E) WALL TO BE REMOVED
	- (E) WALL TO REMAIN

NOTE: WALLS IN LEGEND ENLARGED FOR CLARITY.

ALL DIMENSIONS TO OR FROM (E) STRUCTURE ARE FOR REFERENCE ONLY. CONTRACTOR TO FIELD VERIFY ALL DIMENSIONS AND IS RESPONSIBLE TO CONTACT DESIGNER W/ ANY DISCREPANCIES.

THE EKLUND RESIDENCE

1620 SE WAYERLY DRIVE
MILWAUKEE, WI 53222

PLAN NO:
DRAWN: TF.
DATE: 4/20/2014
SCALE: 1/4"=1'-0"
FILE:

EXISTING FLOOR PLANS

FLOOR PLAN FRAMING NOTES:

- ALL EXTERIOR WINDOW AND DOOR HEADERS TO BE 4 X 10 DF-L NO. 2 UNLESS OTHERWISE NOTED. (UN)
- ALL EXTERIOR WALLS TO BE 2 X 6 STUDS • 16" O.C. AND INTERIOR WALLS TO BE 2 X 4 STUDS • 16" O.C. FOUNDATION FRONT WALLS SHALL BE FRAMED OF 2 X 6 STUDS.
- STANDARD STUD HEIGHT FOR UPPER FLOOR TO BE 9'-0" CEILING HEIGHT.
- STANDARD STUD HEIGHT FOR MAIN FLOOR TO BE 9'-0" CEILING HEIGHT.
- WINDOW AND DOOR HEADER HEIGHTS TO BE 8'-0" ON UPPER FLOOR AND 8'-0" ON LOWER FLOOR. (UN) DOOR OPENINGS AND OTHER OPENINGS TO BE ALIGNED WITH WINDOW HEIGHTS. (UN)
- ALL WOOD IN DIRECT CONTACT WITH CONCRETE TO BE PRESSURE TREATED AND/OR PROTECTED BY 55# FELT MOISTURE BARRIER.
- PROVIDE POLYSTYRENE FOAM TYPE INSULATION AT FLOOR AND PLATE LINES, OPENINGS IN PLATES, CORNER STUD CAVITIES AND AROUND DOOR AND WINDOW ROUGH OPENINGS.
- BEARING FOR JOISTS, SUPPORT MEMBERS, HEADERS, AND BEAMS TO BE 1/2 THE MEMBERS WIDTH AND SOLID BEARING TO FOOTINGS. 2 X JOISTS TO HAVE 1/2 MIN. BEARING U.O.N.
- PROVIDE FIRE BLOCKING, DRAFT STOPS AND FIRE STOPS AS PER 2021 ORSC SECTION 6020.
- BLOCK ALL STUD WALLS AT SHEATHING SPLICES OR AS REQUIRED.
- INTERIOR PASSAGE DOORS TO HAVE A MINIMUM OF (2) 2 X TRIMMERS EACH SIDE OF DOOR AND TO BE CENTERED IN HALLS.
- ALL HOLDINGS, JOIST HANGERS, BEAM HANGERS AND OTHER CONNECTORS TO BE SIMPSON OR EQUAL.
- ALL STUD WALLS SHALL HAVE DOUBLE TOP PLATES OF THE SAME DIMENSION AS THE WALL FRAMING. PLATES SHALL OVERLAP A MINIMUM OF 48" BETWEEN SPLICES WITH AT LEAST (8) 16D NAILS THROUGH BOTH PLATES OR SPLICE.
- DO NOT NOTCH OR DRILL THROUGH ANY SUPPORT COLUMNS, GIRDERS, BEAMS, JOIST SUPPORTING BEARING WALLS OR ANY OTHER CONCENTRATED LOAD BEARING MEMBER UNLESS SPECIFICALLY NOTED ON PLANS. CONTACT DESIGNER IN ANY SUCH SITUATIONS ARISE.
- THIS STRUCTURE TO BE ADEQUATELY BRACED FOR WIND AND GRAVITY LOADS UNTIL THE ROOF, FLOOR AND WALLS HAVE BEEN PERMANENTLY FRAMED TOGETHER AND SHEATHED.

LUMBER SPECIES AND GRADING:

- A. POSTS, BEAMS, HEADERS,
- B. RAFTER JOISTS, CEILING JOISTS, RAFTERS,
- C. SILLS, PLATES, BLOCKING, BRIDGING,
- D. STUDS,
- E. STUDS OVER 16' HIGH,
- F. FLOOR DECKING,
- G. WALL, ROOF SHEATHING,
- H. GLU-LAM BEAMS
- I. PATALEAN STRAND LUMBER (PSL) / MATERIALS
- J. LAMINATED VENEER LUMBER (LVL) MATERIALS


NAILING SCHEDULE:

REFER TO: ORSC 2021 TABLE R6023(1)

WINDOW SCHEDULE

MARK	SIZE & TYPE	QUANTITY
△	NOT USED	-
△	3-1/2"X8" PX MULLED	1
△	4-1/2"X6" PX MULLED	1
△	5-1/2"X6" CSHT-PX	1
△	2-6"X4" CSHT.	1
△	2-6"X6" CSHT.	3
△	3-1/2"X5" PX MULLED	1
△	4-1/2"X5" PX MULLED	1
△	5-1/2"X5" PX MULLED	1
△	6-1/2"X5" PX MULLED	1
△	2-6"X4" CSHT-PX	1
△	2-6"X6" CSHT-PX	1
△	3-1/2"X6" PX MULLED	1
△	4-1/2"X6" PX MULLED	1
△	5-1/2"X6" PX MULLED	1
△	6-1/2"X6" PX MULLED	1
△	2-6"X5" CSHT.	1
△	2-6"X6" CSHT.	1
△	3-1/2"X6" CSHT.	1
△	4-1/2"X6" CSHT.	1
△	5-1/2"X6" CSHT.	1
△	6-1/2"X6" CSHT.	1
△	2-6"X6" CSHT-PX	1
△	3-1/2"X6" CSHT-PX	1
△	4-1/2"X6" CSHT-PX	1
△	5-1/2"X6" CSHT-PX	1
△	6-1/2"X6" CSHT-PX	1

NOTES:
• ALL WINDOWS TO HAVE GRIDS UNO.
• CONTRACTOR TO CONFIRM ALL WINDOW SIZES AND QUANTITIES



FLOOR PLAN FRAMING NOTES CONT..

INSULATION:

1. USE PATH OF 2011 ORSC ENERGY CODE AND THE FOLLOWING INSULATION VALUES TABLE N10(X).

ENERGY COMPLIANCE	PATH 1
WALL INSULATION	R-21/R-23
WALL INSULATION BELOW GRADE	R-15/R-21
FLAT CEILINGS	R-49
VAULTED CEILINGS	R-30
UNDERFLOORS	R-30
SLAB EDGE PERIMETER	R-15
HEATED SLAB INTERIOR	R-10
WINDOWS	U-0.27
WINDOW AREA LIMITATION	N/A
SKYLIGHTS	U-0.50
EXTERIOR DOORS	U-0.20
EXTERIOR DOORS W/ >2.5 FT. GLAZING	U-0.40
FORCED AIR DUCT	R-8

2. INSULATION:

R-49
R-30
R-23
R-15/R-21
R-5 (RIGID)
R-8

ROOF (FLAT CEILING)
ROOF (VAVUL CEILING)
FLOORS OVER UNHEATED SPACES
EXTERIOR WALLS
BASEMENT WALLS (INTERIOR OR EXTERIOR)
CONCRETE FLOOR SLAB EDGES AT PERIMETER UNDER HEATED AREAS.
EXPOSED FURNACE DUCTS IN UNHEATED AREAS.

3. GLAZING/DOORS:

NO LIMITS
WINDOW AREA LIMIT
U-35
U-34
ENTRY DOOR CLASS (24 SQ FT MAX)
U-40 FULL LIGHT GLASS DOOR CLASS
U-20 OTHER DOORS (50% MAX GLAZING)
U-60 SKYLIGHT CLASS (75% MAX OF HEATED SPACE)

4. ALL AIR INFILTRATIONS IN THE EXTERIOR ENVELOPE SHALL BE SEALED INCLUDING WINDOW AND DOOR FRAMES, WALLS, FOUNDATIONS, VENTING AND UTILITY PENETRATIONS. ACCESS DOORS TO CRAWL SPACES AND ATTIC AREAS TO HAVE THE SAME EQUIVALENT RATING OF THE WALL, FLOOR OR CEILING THROUGH WHICH THEY PENETRATE.

5. PROVIDE AN APPROVED INSULATION VAPOR BARRIER WITH A ONE PERM DRY CAP RATING OR LESS AND TO BE INSTALLED ON THE WARM SIDE OF THE INSULATION.

6. INSULATE ALL ACCESS DOOR HATCHES TO CRAWL SPACES AND ATTICS TO THE EQUIVALENT RATING OF THE WALL, FLOOR OR CEILING THROUGH WHICH THEY PENETRATE.

7. ALL EXPOSED INSULATION IS TO HAVE A FLAME SPREAD RATING NOT TO EXCEED 25. A SMOKE-DEVELOPED FACTOR IS TO EXCEED 450 AND CRITICAL RADIANT FLUX NOT LESS THAN 0.72 WATTS PER SQUARE CENTIMETER.

MISCELLANEOUS:

1. EACH BEDROOM TO HAVE A MINIMUM WINDOW OPENING OF 5.1 SQ. FT. WITH A MINIMUM CLEARANCE WIDTH OF 20 INCHES AND A BOTTOM SILL HEIGHT LESS THAN 44 IN. ABOVE FINISHED FLOOR.

2. ALL EXTERIOR WINDOWS ARE TO BE DOUBLE GLAZED AND ALL EXTERIOR DOORS ARE TO BE SOLID CORE WITH WEATHER STRIPPING. PROVIDE 1/2" DEAD BOLT LOCKS ON ALL EXTERIOR DOORS. PROVIDE FEET HOLES @ 54"-64" ABOVE FINISHED EXT. DOOR FLOOR.

3. WINDOW MUST MEET THE U-VALUE OR CLASS REQUIREMENT FOR THE APPROPRIATE ENERGY PATH AND BE LABELED ACCORDINGLY. SITE BUILT WINDOWS MAY BE USED PROVIDED THEY MEET THE CRITERIA AS OUTLINED IN 2011 ORSC SEC III.F.4.

4. WINDOWS ARE TO BE TEMPERED IF THEY ARE WITHIN 18 INCHES OF THE FLOOR, WITHIN A 24 INCH ARCH OF ANY DOOR IN A CLOSED POSITION. GLAZING USED IN RAILINGS, GLAZING IN FIXED OR SLIDING DOORS WHERE THE BOTTOM EDGE IS WITHIN 60 INCHES ABOVE STAIRS, TUB/TUBS, WHIRLPOOLS, AND/OR SHOWERS.

5. SKYLIGHTS ARE TO BE GLAZED WITH TEMPERED GLASS ON OUTSIDE AND LAMINATED GLASS ON INSIDE. FLEXIBLE GLASS TO HAVE A MAX 1" CLEAR SPAN OF 25 INCHES. SKYLITE FRAME IS TO BE ATTACHED TO A 2 X 4 CURE AND TO BE 4 INCHES MINIMUM ABOVE ROOF PLANE. MIN 25LBS. PSF SNOW LOAD ADDITIONAL.

6. ALL TUB AND SHOWER ENCLOSURE DOORS TO BE GLAZED WITH SAFETY GLASS.

7. BATHROOMS AND UTILITY ROOMS ARE TO BE VENTED DIRECTLY TO THE OUTSIDE VIA METAL DUCTING WITH A FAN CAPABLE OF PRODUCING A MINIMUM OF 5 AIR EXCHANGES PER HOUR (% CFM MIN). DRYER AND RANGE HOODS ARE ALSO TO BE VENTED TO THE OUTSIDE. VENTS TO BE PROVIDED WITH BACK-DRAFT DAMPERS.

8. SMOKE DETECTORS SHALL BE INSTALLED IN EACH BEDROOM AND OUTSIDE THE IMMEDIATE VICINITY OF EACH BEDROOM AREA AND ON EACH STORY OF THE DUELING. ALL DETECTORS SHALL BE INTERCONNECTED TO MAIN POWER SOURCE AS THE PRIMARY POWER AND BATTER BACKUP AS SECONDARY POWER. ACTUATION OF ONE ALARM WILL ACTIVATE ALL THE ALARMS AND WILL BE AUDIBLE IN ALL BEDROOMS.

9. ELECTRICAL RECEPTACLES IN BATHROOMS, KITCHENS, EXTERIOR LOCATIONS AND GARAGES SHALL BE GFCI. PER NATIONAL ELECTRICAL CODE REQUIREMENTS.

10. DECESSED LIGHT FIXTURES ARE NOT PERMITTED IN ANY INSULATED CAVITY UNLESS THE FIXTURES ARE LABELED AS BEING SUITABLE (IC LABEL) FOR DIRECT CONTACT WITH INSULATION.

11. ALL DOORS BETWEEN GARAGE AND LIVING AREAS SHALL BE ONE-HOUR FIRE RATED ASSEMBLIES WITH 1-1/4" SOLID CORE DOOR OR CODE APPROVED EQUAL WITH A SELF-CLOSING MECHANISM.

12. USE 1/2" GYPSUM BOARD IN HOUSE WALLS AND CEILINGS AND UNDER STAIRS. USE 5/8" TYPE-X GYPSUM BD. ON WALLS AND CEILINGS BETWEEN GARAGE AND LIVING AREAS. PROVIDE 1/2" WATERPROOF GYPSUM BD. ABOVE ALL SHOWER AND TUB/SHOULER AND TUB/SHOULER UNITS AND ANY WATER SPLASH AREAS.

13. ALL FIREPLACE OPENINGS SHALL HAVE TEMPERED GLASS DOORS. PROVIDE OUTSIDE COMBUSTION AIR VENTS WITH SCREENS AND BACK-DAMPER FOR FIREPLACES, WOOD STOVES AND ANY APPLIANCES WITH OPEN FLAME.

14. APPLIANCES PRODUCING A SPARK, GLOW OR FLAME CAPABLE OF IGNITING FLAMMABLE VAPORS SHALL NOT BE INSTALLED IN A GARAGE UNLESS THE PILOTS, BURNERS, HEATING ELEMENTS OR SWITCHES ARE AT LEAST 18 INCHES ABOVE THE FLOOR.

15. PROVIDE 80% MIN. EFFICIENT NATURAL GAS FURNACE WITH BACKDRAFT DAMPER AND NATURAL GAS HOT WATER HEATER WITH BACKDRAFT DAMPER. PROVIDE R-4 INSULATION AROUND HOT WATER LINER IN UNHEATED AREAS. ELEVATE FLAME IN UNITS 12' ABOVE FINISH FLOOR.

16. ALL WINDOW HOURS TO BE 4 X 10 UNO.

17. FRONT PORCH TO BE CONCRETE SLAB, UNO.

IMPORTANT DISCLOSURE

- PLEASE READ:


THE PLANS YOU HAVE PURCHASED ARE FOR THE CONSTRUCTION USE ONLY. UNDER NO CIRCUMSTANCES IS IT LEGAL TO BUILD FROM THESE PLANS FOR ANY OTHER PURPOSE. THE WRITER AND OWNER OF THESE PLANS IS THE DESIGNER FOWLER HOME DESIGN LLC. THESE PLANS ARE COPIRIGHTED AND IT IS A VIOLATION OF FEDERAL LAW TO COPY THESE PLANS. FOWLER HOME DESIGN LLC WILL FULLY PROSECUTE ANYONE WHO COPIES THESE PLANS. FOWLER HOME DESIGN LLC FURTHERMORE IT IS UNDERSTOOD THAT IT IS COMPLETELY THE RESPONSIBILITY OF THE CONTRACTOR TO CONSTRUCT THE HOUSE ACCORDING TO THE PLANS AND SPECIFICATIONS AND WITHIN THE CONFINES OF THE GOVERNING JURISDICTION. FOWLER HOME DESIGN LLC TAKES NO RESPONSIBILITY FOR THE CONFORMANCE OF THIS PLAN TO ANY CODE OR ANY BUILDING SITE.

WALL LEGEND	
	- NEW (N) 2x WALL
	- EXISTING (E) WALL TO BE REMOVED
	- (E) WALL TO REMAIN

NOTE: WALLS IN LEGEND ENLARGED FOR CLARITY.

ALL DIMENSIONS TO OR FROM (E) STRUCTURE ARE FOR REFERENCE ONLY. CONTRACTOR TO FIELD VERIFY ALL DIMENSIONS AND IS RESPONSIBLE TO CONTACT DESIGNER W/ ANY DISCREPANCIES.

NOTES: ALL WINDOWS TO HAVE GRIDDED UNO. CONTRACTOR TO CONFIRM ALL WINDOW SIZES AND AVAILABILITIES.



WINDOW SCHEDULE

MARK	SIZE & TYPE	QUANTITY
	NOT USED	-
	3-2/6X8/0 PX MULLED	1
	4-2/6X8/0 PX-CMT-CMT-PX	1
	2/6X4/0 CMT.	1
	2/6X6/0 CMT.	3
	3-2/6X8/0 MULLED PX-CMT-PX	1
	2/6X5/0 CMT.	5
	3-2/6X8/0 MULLED PX-CMT-PX	1
	2-2/6X6/0 CMT. MULLED	1
	2/6X5/0 CMT. MULLED	7
	2-2/6X6/0 CMT. MULLED	1
	2/6X5/0 PX	8
	3-2/6X3/0 MULLED PX-CMT-PX	1
	2-2/6X3/0 MULLED PX-CMT-PX	1
	4/6X5/0 PX	3
	4-2/6X4/0 MULLED PX-CMT-CMT-PX	1

UPPER FLOOR PLAN

2,054 SQ. FT. EXISTING
2,420 SQ. FT. UPPER TOTAL
342 SQ. FT. NEW ADDITION

1/4" = 1'-0"

THESE PLANS AND DESIGNS HEREIN ARE COPIRIGHTED UNDER FEDERAL LAW BY FOWLER HOME DESIGN LLC 2012



IMPORTANT DISCLOSURE
- PLEASE READ:

THE PLANS YOU HAVE PURCHASED ARE FOR THE CONSTRUCTION OF ONE HOME ONLY. UNDER NO CIRCUMSTANCES IS IT LEGAL TO BUILD MORE THAN ONE HOME FROM THESE PLANS WITHOUT THE WRITTEN CONSENT FROM THE DESIGNER. TROY FOWLER, DESIGNER OF THESE PLANS, RESERVES THE EXCLUSIVE RIGHT TO REPRODUCE THESE PLANS. IT IS AN VIOLATION OF FEDERAL COPYRIGHT LAWS TO REPRODUCE THESE PLANS OR ANY PORTION THEREOF. IT IS UNDERSTOOD THAT IT IS COMPLETELY THE RESPONSIBILITY OF THE CONTRACTOR TO ENSURE THAT THE HOME DESCRIBED HEREIN ON ANY PARTICULAR SITE AND IN ACCORDANCE WITH THE GOVERNING JURISDICTION. FOWLER HOME DESIGN LLC, TAKES NO RESPONSIBILITY FOR THE CONFORMANCE OF THIS PLAN TO ANY CODE OR ANY BUILDING SITE.

WALL LEGEND	
	- NEW (N) 2x WALL
	- EXISTING (E) WALL TO BE REMOVED
	- (E) WALL TO REMAIN

NOTE: WALLS IN LEGEND ENLARGED FOR CLARITY.

ALL DIMENSIONS TO OR FROM (E) STRUCTURE ARE FOR REFERENCE ONLY. CONTRACTOR TO FIELD VERIFY ALL DIMENSIONS AND IS RESPONSIBLE TO CONTACT DESIGNER W/ ANY DISCREPANCIES.

LOWER FLOOR PLAN

1,226 SQ. FT. EXISTING

1/4"=1'-0"

FOUNDATION NOTES:

- 1. FOUNDATION FOOTINGS, CANT. FOOTING UNDER PONWALL TO BEAR ON UNDISTURBED SOIL WITH MINIMUM DEPTH OF BOTTOM OF FOOTING TO BE 18" BELOW FINAL GRADE. SOIL BEARING PRESSURE ASSUMED TO BE 3000 PSI.
- 2. ALL EXCESS FRAMING MATERIAL TO BE EXPORTED FROM THIS SITE TO AN APPROVED DISPOSAL LOCATION.
- 3. EXCAVATE SITE TO PROVIDE A MINIMUM OF 18" CLEARANCE UNDER ALL GIRDERS.
- 4. CLEAN ALL FOOTING EXCAVATIONS OF LOOSE AND ORGANIC MATERIALS.
- 5. MAXIMUM SLOPE OF CUTS AND FILLS TO BE TWO (2) HORIZONTAL TO ONE (1) VERTICAL FOR BUILDINGS, STRUCTURES, FOUNDATIONS, AND RETAINING WALLS.
- 6. DO NOT BACKFILL FOUNDATION WALLS UNTIL MAIN FLOOR INCLUDING SUB-FLOORING AND WALL DIAPHRAGMS ARE IN PLACE AND FULLY NAILED AND ANCHORED AND FOUNDATION WALLS HAVE BEEN CAST AND CURED.

- 7. CONCRETE:
 BASEMENT AND FOUNDATIONS 6 SACK/YD. 4' MAX SLUMP 3000 PSI
 WALLS AND FOOTINGS NOT EXPOSED TO LEATHER 6 SACK/YD. 4' MAX SLUMP 3000 PSI
 ON GRADE
 BASEMENT AND EXTERIOR SLABS 6 SACK/YD. 4' MAX SLUMP 3000 PSI
 ON GRADE
 BASEMENT WALLS, FOUNDATIONS 6 SACK/YD. 4' MAX SLUMP 3000 PSI
 AND FOOTINGS EXPOSED TO WEATHER
 PORCH STEPS, CARPORT AND OTHER EXTERIOR SLABS DIRECTLY EXPOSED TO WEATHER
 5% - 1% MAX. AIR TRAINED.

- 8. ALL CONCRETE SHALL DEVELOP A MINIMUM COMPRESSIVE STRENGTH AT 28 DAYS.
- 9. ALL CONCRETE FORM, SHORING AND POURING METHODS SHALL CONFORM TO CURRENT ACI STANDARDS.
- 10. ALL FOUNDATIONS TO BE 8' CONCRETE WALLS ON 1' X 8' MIN. CONCRETE FOOTINGS REFER TO FOUNDATION PLAN FOR ADDITIONAL REQUIREMENTS. ALL FOUNDATIONS OVER 40" HIGH REQUIRE TO BE ENGINEERED CONCRETE WALLS AND FOOTINGS.

- 11. ALL FILL UNDER GRADE SUPPORTED SLABS TO BE A MINIMUM OF 4' GRANULAR MATERIAL (3/4"-2") COMPACTED TO 95% MINIMUM.

- 12. CONCRETE SLABS TO HAVE TOOLED CONTROL JOINTS AT 15 FT. MAXIMUM INTERVALS EACH WAY.

- 13. CONCRETE SIDEWALKS TO HAVE 3/4" TOOLED JOINTS AT 5 FT. OC. MINIMUM.

- 14. PROVIDE 12" X 8" CLOSEABLE SCREENED FOUNDATION AIR VENTS WITH 18" CONDUCTION REINFORCED CONCRETE SHEATH. SPACED WITHIN 12" OF OUTSIDE CORNERS AND EQUALLY DISTRIBUTED AROUND PERIMETER OF CRAWL SPACE. (A MINIMUM OF ONE (1) SQUARE FOOT OF VENTILATION AREA FOR EACH 80 SF. OF CRAWL AREA REQUIRED).

- 15. PROVIDE 1/2" DIA. X 10' ANCHOR BOLTS 4' O.C. U.L.O. ON PRESSURE TREATED NO. 3 MILD SILLS. ANCHOR BOLTS TO BE 1" MINIMUM EMBEDMENT INTO CONCRETE WALLS. AT LEAST TWO (2) BOLTS ARE REQUIRED ON EACH SILL AND 12" MINIMUM FROM SILL SPLICES. PROVIDE FOAM INSUL. BUTT-SILL PL. 4 FOUND. WALL.

- 16. REFER TO SIMPSON SPECIFICATIONS FOR BOLT DIAMETER AND MINIMUM IMBIMENT LENGTH ON ALL ANCHOR BOLTS AND SIMPSON STRAP-TIE HOLDOWNS.

17. REBAR SCHEDULE:

- REBAR TO BE LOCATED AT HOLDOWN LOCATIONS ONLY OR AS SHOWN ON PLAN OR REQUIRED BY CODE.

MINIMUM REQUIREMENTS WHERE REBAR IS REQUIRED.

- FOOTINGS: (1) #4 BAR HORIZONTAL CONTINUOUS, 4' CLEAR BOTTOM.
 FOUNDATIONS: (1) #4 BAR TOP HORIZONTAL WITH #4 BARS VERTICAL AT 48" C.C. HOOKED AND TIED TO FOOTING BARS AND TIED TO TOP FOUNDATION BAR.

- 18. REINFORCING BARS TO BE DEFORMED BARS CONFORMING TO ASTM A-615 GRADE 60. WELDED WIRE MESH TO BE A-165.

- 19. REINFORCEMENT SHALL BE ACCURATELY PLACED AND SUPPORTED BY CONCRETE, METAL OR OTHER APPROVED CHARS, SPACERS, OR TIES AND SECURE AGAINST DISPLACEMENT DURING CONCRETE PLACEMENT.

- 20. REINFORCEMENT SHALL BE BENT COLD AND SHALL NOT BE WELDED.

- 21. ALL LAPS AND SPLICES ON #4 REBAR TO BE 24" MINIMUM, UNO.

- 22. STAINLESS ANCHOR BOLTS TO BE INSTALLED PER MANUF. PRIOR TO POURING FOOTINGS.

- 23. EXTEND HEIGHT TO FRONT GARAGE CONCRETE STEW WALLS SO THE TOP OF WALL TO TOP OF GARAGE DOOR HEADER DOES NOT EXCEED 8'-0" MAX.

- 24. GARAGE FLOOR TO BE 4" 3000 PSI MINIMUM CONCRETE SLAB ON 4" MINIMUM CLEAN CONCRETE FILL WITH A 2" SLOPE (1/8" PER FT. MIN) TOWARD OPENING AS REQUIRED FOR DRAINAGE. PROVIDED TOOLED CONTROL JOINTS AT APPROXIMATELY 12FT. O.C. EA. WAY.

- 25. PROVIDE 1" MIN. 3" DIA. X 36" HIGH STEEL PROTECTIVE POST IN FRONT OF FURNACE AND HOT WATER HEATER IN A 1" DIA. X 24" DEEP CONCRETE FOOTING. INSTALL IF REQUIRED FOR PROTECTION FROM CAR. SEE DET. 8/D1.

- 26. PROVIDE BLOCK CUTS FOR DRYER VENTS AND 18" X 18" BLOCK OUT AT FOUNDATION WALL FOR MECH. PLUMB. VERIFY SIZE AND PLACEMENT WITH BUILDER AND/OR SUBCONTRACTORS PRIOR TO INSTALL.

- 27. PROVIDE A 3" DIA. PVC PIPE IN FOUNDATION WALL FOR ELECTRICAL SERVICE. VERIFY PLACEMENT WITH BUILDER/ SUBCONTRACTOR.

- 28. PROVIDE A 4" DIA. PVC LOW POINT CRAWL SPACE DRAIN THROUGH FOUNDATION WALL. BLOCKOUT. DRAIN TO BE SLOPED FOR GRAVITY DRAINAGE AND CONNECTED TO AN APPROVED STORM DRAIN SYSTEM.

- 29. COVER ENTIRE CRAWL AREA WITH 6-MIL BLACK POLYETHYLENE VAPOR BARRIER AND EXTEND UP WALLS TO MID SILLS. LAP SEAMS 12" MIN.

- 30. ALL WOOD IN CONTACT WITH CONCRETE TO BE PRESSURE TREATED AND/OR PROTECTED BY 55# FELT MOISTURE BARRIER.

- 31. ALL GIRDERS AND BEAM POCKETS TO HAVE A 1/2" AIR SPACE AT SIDE AND END WITH A 3" MIN BEARING ON CONCRETE PLACED ON A 55# ASPHALT SHINGLE.

- 32. ALL HOLDOWNS, JOIST HANGERS AND BEAM HANGERS TO BE SIMPSON OR EQUAL.

- 33. PROVIDE A 24" X 30" CRAWL ACCESS (80" X 4' MIN) FROM OUTSIDE OR THROUGH FLOOR PIPES, DUCTS AND OTHER CONSTRUCTION MUST NOT OBSTRUCT THE ACCESS.

- 34. FLOOR CONSTRUCTION TO BE:
 1 1/8" DECKING OR EQUAL ON I-JOISTS FOR MANUF. ON 1X6 FORTAILS OVER 8X16 CONTINUOUS FOOTINGS.

FOOTING SCHEDULE			
FTNG.	LOAD LBS	FOOTING SIZE	REBAR
F1	3,300*	18"X18"X10"	(2) #4 E/W
F2	6,000*	24"X24"X10"	(2) #4 E/W
F3	9,300*	30"X30"X10"	(3) #4 E/W
F4	13,500*	36"X36"X12"	(3) #4 E/W
F5	18,300*	42"X42"X12"	(4) #4 E/W
F6	24,000*	48"X48"X12"	(4) #4 E/W
F7	28,000*	52"X52"X12"	(5) #4 E/W
F8	40,000*	64"X64"X14"	(5) #4 E/W
F9	50,000*	72"X72"X16"	(6) #4 E/W


TOP OF ALL HOLD DOWN BOLTS MUST EXTEND ABOVE ULTIMATE EARTH FRICTION LINE WHICH IS 6" ABOVE TOP OF FDN. WALL.

IMPORTANT DISCLOSURE
- PLEASE READ:

The plans you have purchased are for the construction of the building or structure indicated. Under no circumstances is it legal to build from these plans more than once without the written permission of the original designer. These plans are copyrighted and it is a violation of Federal Law to copy or reproduce them. FOWLER HOME DESIGN LLC WILL PURSUE PROSECUTE ANY VIOLATION OF ITS COPYRIGHTED DESIGN AND PLANS. INDIVIDUAL CONTRACTORS AND CONSTRUCTION COMPANIES ARE RESPONSIBLE FOR THE CONTRACTOR TO CONSTRUCT THE BUILDING OR STRUCTURE ON THE BASIS OF THE PLANS AND CODES OF THE GOVERNING JURISDICTION. FOWLER HOME DESIGN LLC TAKES NO RESPONSIBILITY FOR THE CONSTRUCTION OF THIS PLAN TO ANY CODE OR ANY BUILDING SITE.

SEE STRUC. ENGR. SHEETS

CONTRACTOR TO CONFIRM EXIST. CONDITIONS,
& INFORM DESIGNER OF ANY DISCREPANCIES, TYP.



LOWER FLOOR FRAMING & FDN PLAN

1/4"=1'-0"

FOUNDATION NOTES:

1. FOUNDATION FOOTINGS, CONT. FOOTING UNDER PONYLWALL TO BEAR ON UNDISTURBED SOIL WITH MINIMUM DEPTH OF BOTTOM OF FOOTING TO BE 18" BELOW FINAL GRADE. SOIL BEARING PRESSURE ASSUMED TO BE 1500 PSI.
2. ALL EXCESS FRAMING MATERIAL TO BE EXPORTED FROM THIS SITE TO AN APPROVED DISPOSAL LOCATION.
3. EXCAVATE SITE TO PROVIDE A MINIMUM OF 18" CLEARANCE UNDER ALL GIRDERS.
4. CLEAN ALL FOOTING EXCAVATIONS OF LOOSE AND ORGANIC MATERIALS.
5. MAXIMUM SLOPE OF CUTS AND FILLS TO BE TWO (2) HORIZONTAL TO ONE (1) VERTICAL FOR BUILDINGS, STRUCTURES, FOUNDATIONS, AND RETAINING WALLS.
6. DO NOT BACKFILL FOUNDATION WALLS UNTIL MAIN FLOOR INCLUDING SUB-FLOORING AND WALL DIAPHRAGMS ARE IN PLACE AND FULLY NAILED AND ANCHORED AND FOUNDATION WALLS HAVE BEEN CAST AND CURED.
7. CONCRETE:
 BASEMENT AND FOUNDATIONS 6 SACK/YD. 4" MAX SLUMP 3000 PSI
 BASEMENT AND INTERIOR SLABS 6 SACK/YD. 4" MAX SLUMP 3000 PSI
 ON GRADE
 BASEMENT AND INTERIOR SLABS 6 SACK/YD. 4" MAX SLUMP 3000 PSI
 ON GRADE
 EXTERIOR WALLS, FOUNDATIONS AND FOOTINGS EXPOSED TO LEATHER.
 PORCHES, STEPS, CARPORT AND OTHER EXTERIOR SLABS DIRECTLY EXPOSED TO WEATHER 1 SACK/YD. 4" MAX SLUMP 3500 PSI
 5% - IN MAX. AIR ENTRAINED.
8. ALL CONCRETE SHALL DEVELOP A MINIMUM COMPRESSIVE STRENGTH AT 28 DAYS.
9. ALL CONCRETE FORMS, SHORING AND POURING METHODS SHALL CONFORM TO CURRENT ACI STANDARDS.
10. ALL FOUNDATIONS TO BE 8" CONCRETE WALLS ON 16" X 8" MIN. CONCRETE FOOTINGS REFER TO FOUNDATION PLAN FOR ADDITIONAL REQUIREMENTS. ALL FOUNDATIONS OVER 48" HIGH REQUIRE TO BE ENGINEERED CONCRETE WALLS AND FOOTINGS.
11. ALL FILL UNDER GRADE SUPPORTED SLABS TO BE A MINIMUM OF 4" GRANULAR MATERIAL (3/4"-2") COMPACTED TO 95% MINIMUM.
12. CONCRETE SLABS TO HAVE TOOLED CONTROL JOINTS AT 15 FT. MAXIMUM INTERVALS EACH WAY.
13. CONCRETE SIDEWALKS TO HAVE 3/4" TOOLED JOINTS AT 5 FT. O.C. MINIMUM.
14. PROVIDE (5) 18" X 8" CLOSEABLE SCREENED FOUNDATION AIR VENTS WITH 1/8" CORROSION RESISTANT SCREENED WIRE MESH. SPACE WITHIN 36" OF OUTSIDE CORNERS AND EQUALLY DISTRIBUTED AROUND PERIMETER OF CRAWLSPACE. (A MINIMUM OF ONE (1) SQUARE FOOT OF VENTILATION AREA FOR EACH 50 SQ. FT. OF CRAWL AREA REQUIRED).
15. PROVIDE 1/2" DIA X 10' ANCHOR BOLTS A307 GRADE # 6-8" O.C. UNO. ON PRESSURE TREATED CI 3" MID SILLS. ANCHOR BOLTS TO BE A MINIMUM EMBEDMENT INTO CONCRETE WALLS. AT LEAST TWO BOLTS ARE REQUIRED ON EACH SILL AND 12" MINIMUM FROM SILL SPACER. PROVIDE FOAM INSUL BLASTILL FL. 4 FOUND. WALL.
16. REFER TO SIMPSON SPECIFICATIONS FOR BOLT DIAMETER AND MINIMUM IMBEMENT LENGTH ON ALL ANCHOR BOLTS AND SIMPSON STRAP-TIE HOLDOWNS.
17. REBAR SCHEDULE:
 REBAR TO BE LOCATED AT HOLDOWN LOCATIONS ONLY OR AS SHOWN ON PLAN OR REQUIRED BY CODE.
 MINIMUM REQUIREMENTS WHERE REBAR IS REQUIRED.
 FOOTINGS: (1) 1/4" BAR HORIZONTAL CONTINUOUS, 4" CLEAR BOTTOM.
 FOUNDATIONS: (1) 1/4" BAR HORIZONTAL WITH 4 BARS VERTICAL, AT 16" O.C. HOOKED AND TIED TO FOOTING BARS AND TIED TO TOP FOUNDATION BAR.
18. REINFORCING BARS TO BE DEFORMED BARS CONFORMING TO ASTM A-615 GRADE 60. WELDED WIRE MESH TO BE 18#.
19. REINFORCEMENT SHALL BE ACCURATELY PLACED AND SUPPORTED BY CONCRETE, METAL, OR OTHER APPROVED CHAIRS, SPACERS, OR TIES AND SECURE AGAINST DISPLACEMENT DURING CONCRETE PLACEMENT.
20. REINFORCEMENT SHALL BE BENT COLD AND SHALL NOT BE WELDED.
21. ALL LAPS AND SPLICES ON 4 REBAR TO BE 24" MINIMUM UNO.
22. #12B ANCHOR BOLTS TO BE INSTALLED PER MANUF. PRIOR TO POURING FOOTINGS.
23. EXTEND HEIGHT TO GARAGE CONCRETE STEM WALLS SO THE TOP OF WALL TO TOP OF GARAGE DOOR HEADER DOES NOT EXCEED 8'-0" MAX.
24. GARAGE FLOOR TO BE 4" 3500 PSI MINIMUM CONCRETE SLAB ON 4" MINIMUM CLEAN COMPACTED FILL WITH A 2" SLOPE (1/8" PER FT. MIN) TOWARD OPENING AS REQUIRED FOR DRAINAGE. PROVIDE TOOLED CONTROL JOINTS AT APPROXIMATELY 10FT. O.C. EACH WAY.
25. PROVIDE (1) MIN 3" DIA X 36" HIGH STEEL PROTECTIVE POST IN FRONT OF FURNACE AND HOT WATER HEATER IN A 12" DIA X 24" DEEP CONCRETE FOOTING. (INSTALL IF REQUIRED FOR PROTECTION FROM CARS. SEE DET. B/D)
26. PROVIDE BLOCK OUTS FOR DRYER VENTS AND 18" X 18" BLOCK OUT AT FOUNDATION WALL FOR MECH. PLN. VERIFY SIZE AND PLACEMENT WITH BUILDER AND OR SUBCONTRACTORS PRIOR TO INSTALL.
27. PROVIDE A 3" DIA PVC PIPE IN FOUNDATION WALL FOR ELECTRICAL SERVICE. VERIFY PLACEMENT WITH BUILDER/ SUBCONTRACTOR.
28. PROVIDE A 1/4" DIA PVC LOW POINT CRAWL SPACE DRAIN THROUGH FOUNDATION WALL. BLOCKOUT DRAIN TO BE SLOPED FOR GRAVITY DRAINAGE AND CONNECTED TO AN APPROVED STORM DRAIN SYSTEM.
29. COVER ENTIRE CRAWL AREA WITH 6-MIL BLACK POLYETHYLENE VAPOR BARRIER AND EXTEND UP WALLS TO MID SILLS. LAP SEAMS 12" MIN.
30. ALL WOOD IN CONTACT WITH CONCRETE TO BE PRESURE TREATED AND/OR PROTECTED BY 55# FELT MOISTURE BARRIER.
31. ALL GIRDERS AND BEAM POCKETS TO HAVE A 12" AIR SPACE AT SIDE AND END WITH A 3" MIN BEARING ON CONCRETE PLACED ON A 55# ASPHALT SHINGLE.
32. ALL HOLDOWNS, JOIST HANGERS AND BEAM HANGERS TO BE SIMPSON OR EQUAL.
33. PROVIDE A 12" X 36" CRAWL ACCESS (9" X 24" MIN) FROM OUTSIDE OR THROUGH FLOOR PIPES, DUCTS AND OTHER CONSTRUCTION MUST NOT OBSTRUCT THE ACCESS.
34. FLOOR CONSTRUCTION TO BE:
 1 1/8" DECKING OR EQUAL ON I-JOISTS PER MANUF.
 ON 2X6 FORTWALLS OVER 8X16 CONTINUOUS FOOTINGS

FDN VENTILATION CALCULATIONS:

VENTILATION REQUIRED IN CRAWL SPACE AREA:			
948 SQ. FT. X 144 SQ. IN. = 1380 = 910 TOTAL SQ. IN. REQUIRED			
LOCATION:	REQ. SQ. IN.	NO. OF VENTS:	VENT SIZE: TOTAL SQ. IN.
FDN	910	9	108 sq.in. 912


TOP OF ALL HOLD DOWN BOLTS MUST EXTEND ABOVE FOUNDATION WALL AND 12" MINIMUM (6" ABOVE TOP OF FOUND. WALL).

IMPORTANT DISCLOSURE
- PLEASE READ -

THE PLANS YOU HAVE PURCHASED ARE FOR THE CONTRACTOR USE ONLY. UNDER NO CIRCUMSTANCES IS IT LEGAL TO BUILD FROM THESE PLANS WITHOUT THE WRITTEN CONSENT FROM THE DESIGNER. THOSE WHO COPY THESE PLANS ARE VIOLATING THE LAW. FOWLER HOME DESIGN LLC WILL FULLY PROSECUTE ANYONE WHO COPIES THESE PLANS. THEREFORE IT IS UNDERSTOOD THAT IT IS COMPLETELY THE RESPONSIBILITY OF THE CONTRACTOR TO CONSTRUCT THE BUILDING IN ACCORDANCE WITH THE PLANS AND WITHIN THE CONFINES OF THE GOVERNING JURISDICTION. FOWLER HOME DESIGN LLC TAKES NO RESPONSIBILITY FOR THE COMPLIANCE OF THIS PLAN TO ANY CODE OR ANY BUILDING SITE.

SEE STRUC. ENGR. SHEETS


SEE JOIST ENGR. SHEETS FROM MANUF.

CONTRACTOR TO CONFIRM EXIST. CONDITIONS,
& INFORM DESIGNER OF ANY DISCREPANCIES, TYP.

FOOTING SCHEDULE			
FTNG.	LOAD LBS	FOOTING SIZE	REBAR
F1	3,300*	18"X18"X10"	(2) #4 E/W
F2	6,000*	24"X24"X10"	(2) #4 E/W
F3	9,300*	30"X30"X10"	(3) #4 E/W
F4	13,500*	36"X36"X12"	(3) #4 E/W
F5	18,300*	42"X42"X12"	(4) #4 E/W
F6	24,000*	48"X48"X12"	(4) #4 E/W
F7	28,000*	52"X52"X12"	(5) #4 E/W
F8	40,000*	64"X64"X14"	(5) #4 E/W
F9	50,000*	72"X72"X16"	(6) #4 E/W

MAIN FLOOR FRAMING & FDN PLAN

1/4"=1'-0"




RADON CONTROL METHOD C.

FLOOR FRAMING NOTES:

1. SEE FLOOR JOIST OR TRUSS MANUF. SHEET.
2. FLOOR JOIST SPANS ARE BASED ON A 40' LL + 15' DL + 55' TL DEFLECTION LIMITED.
3. PROVIDE BLOCK CUTS FOR DOWNT DRAFT COOK TOPS, DRYER VENTS, MECH FLUES, AND ACCESSSES. VERIFY SIZE AND PLACEMENT WITH BUILDER/ SUBCONTRACTORS PRIOR TO INSTALL.
4. ALL WOOD IN DIRECT CONTACT WITH CONCRETE TO BE PRESSURE TREATED AND/OR PROTECTED BY 55' FELT MOISTURE BARRIER.
5. ALL GIRDERS IN CONCRETE BEAM POCKETS TO HAVE A 1/2" AIR SPACE AT SIDES AND ENDS WITH A 3" MIN BEARING ON CONCRETE PLACED ON A 55' FELT MOISTURE BARRIER.
6. ALL HOLDOWNS, JOIST HANGERS AND BEAM HANGERS TO BE 'SIMPSON' OR EQUAL.
7. REFER TO BORNE CASCADE TECHNICAL SUPPORT FOR BEAMS + HEADER HANGERS.
8. PROVIDE SOLID BLOCKING UNDER ALL UPPER LEVEL BEARING WALLS AS SHOWN ON PLAN.
9. PROVIDE A CONTINUOUS RIM JOIST AROUND PERIMETER OF EXTERIOR WALLS. RIM JOIST TO BE OF THE SAME SIZE AND MATERIAL TYPE AS FLOOR JOISTS UNLESS OTHERWISE NOTED. FASTEN RIM JOISTS TO WALL BELOW WITH AT LEAST 16D TOE-NAILS AT 8' O.C.
10. PROVIDE 1 1/8" T x 6 CDX (4PA 3/4x6) FLYWOOD OR APPROVED EQUAL SUB-FLOOR SHEATHING. GLUE AND FASTEN SHEATHING WITH 10D COMMON NAILS AT 6' O.C. AT ALL EDGES AND 10D COMMON NAILS AT 12' O.C. AT ALL INTERMEDIATE FRAMING MEMBERS.
11. SUB-FLOOR SHEATHING TO EXTEND OUTWARD TO ALL PERIMETER EXTERIOR WALLS BELOW.
12. VERIFY LOCATION OF ALL PLUMBING DRAINS AND OFFSET FLOOR JOISTS UP TO 3' O.C. MAXIMUM TO AVOID NOTCHING AND CUTTING OF JOISTS.
13. BEARING FOR JOISTS, SUPPORT MEMBERS, HEADERS AND BEAMS TO BE 1/2 THE MEMBERS WIDTH AND SOLID BEARING TO FOOTINGS. 2 X JOISTS TO HAVE 1-1/2" MIN BEARING.
14. DO NOT NOTCH, BORE OR DRILL THROUGH ANY SUPPORT COLUMNS, GIRDERS, BEAMS, JOIST SUPPORTING BEARING WALLS OR ANY OTHER CONCENTRATED LOAD BEARING MEMBER UNLESS SPECIFICALLY NOTED ON PLANS. CONTACT DESIGNER IF QUESTIONS ARISE.
15. PROVIDE DOUBLE RIM JOISTS AT ALL EXTERIOR WALLS PARALLEL TO JOISTS AND AS SHOWN ON PLAN.
16. LAP FLOOR JOISTS A MINIMUM OF 6' EACH WAY AT ALL INTERIOR BEARING MEMBERS. NAIL LAPS WITH (3) 16D AND TO BEARING MEMBER WITH (3) 16D.
17. JOISTS SHALL BE SUPPORT LATERALLY BY BLOCKING OR BRIDGING AT JOIST MID-SPAN AT INTERVALS NOT EXCEEDING 10 FEET.

SYMBOLS LEGEND:

	DENOTES (2) CRIPPLE STUDS (2x WIDTH OF WALL) UNO.
	BEAM SCHEDULE CALLOUT.
	BEARING WALL DETAIL.
	DETAIL CALLOUT OVER SHEET *.
	4X10 HEADER (UNO).



THE EKLUND RESIDENCE
1620 SE WAYERLY DRIVE
MILWAUKEE, WI 53222

PLAN No.:
DRAWN: TF.
DATE: 1/17/2024
SCALE: 1/4"=1'-0"
FILE:

UPPER FL.
FRAMING
PLAN

IMPORTANT DISCLOSURE
- PLEASE READ:

THE PLANS YOU HAVE PURCHASED ARE FOR THE CONSTRUCTION ONE HOME ONLY.
IT IS ILLEGAL TO BUILD MORE THAN ONE HOME FROM THESE PLANS MORE THAN ONCE WITHOUT THE WRITTEN PERMISSION OF THE DESIGNER.
THESE PLANS ARE COPYRIGHTED AND IT IS A VIOLATION OF FEDERAL COPYRIGHT LAW TO REPRODUCE THESE PLANS WHOLLY OR IN PART, OR TO DISSEMINATE ANY VIOLATION OF ITS COPYRIGHTED DESIGNS AND PLANS.
ANYONE WHO HAS PURCHASED THESE PLANS IS SOLELY RESPONSIBLE FOR THE CONTRACTOR TO CONSTRUCT THE HOME DESCRIBED THEREIN ON ANY PARTICULAR SITE AND IN ACCORDANCE WITH ALL APPLICABLE CODES.
FOWLER HOME DESIGN LLC TAKES NO RESPONSIBILITY FOR THE COMPLIANCE OF THIS PLAN TO ANY CODE OR ANY BUILDING SITE.

SEE STRUC. ENGR. SHEETS

CONTRACTOR TO CONFIRM EXIST. CONDITIONS,
& INFORM DESIGNER OF ANY DISCREPANCIES, TYP.

UPPER FLOOR FRAMING PLAN

1/4"=1'-0"

40

THESE PLANS AND DESIGNS
HEREIN ARE COPYRIGHTED
UNDER FEDERAL LAW BY
FOWLER HOME DESIGN
LLC 2024

ROOF FRAMING NOTES:

1. ROOFING MATERIAL TO BE 16' STANDING SEAM METAL ROOF AND ARCHITECTURAL COMPOSITION ROOFING WITH RAIN AND ICE SHIELD NAILING PER MANUFACTURED INSTRUCTIONS FOR AN 80 MPH MIN. UND AREA.
2. ROOF PITCH AS SHOWN ON PLAN.
3. ROOF DESIGN TO BE MANUFACTURED ROOF TRUSSES #24" O.C. UNO. MANUFACTURER TO SUPPLY DESIGN, ENGINEERING SPECIFICATIONS AND LAYOUT.
4. MANUFACTURED TRUSSES SHALL BE LATERALLY BRACED ACCORDING TO APPROPRIATE MANUFACTURER'S ENGINEERED DESIGN.
5. TRUSS MEMBERS SHALL NOT BE NOTCHED, BORED, DRILLED THROUGH OR ALTERED UNLESS DESIGNED BY AND SHOWN ON MANUFACTURER'S SPECIFICATIONS.
6. ALL RAFTERS & CEILING JOISTS TO BE 2 X 10'-0" OR BETTER AS PER TABLE NOTED BELOW AND PER ROOF FRAMING PLAN. SPAN DISTANCE BASED ON SIMPLE UNIFORM LOADING AND PER ORSCC 2021 TABLES 802.4(2) & 802.5(3).
7. ALL HIPS, VALLEYS AND RIDGES TO BE NOT LESS IN DEPTH THAN THE CONNECTION END OF THE RAFTER, UNO.
8. ALL FLAT-ON VALLEY'S TO BE 2 X 10' WITH (2) 16D AT EACH RAFTER/TRUSS.
9. ALL EAVE OVERHANGS TO BE CLOSED TYPE AT 24". ALL CORNICE TO BE 12", UNO.
10. EAVES TO BE OPEN TYPE GUTTERS WITH A 3" X 6" GALVANIZED FACHA GUTTER ON A 2 X 10 FACHA BD, UNO. AND 3" GALVANIZED DOWNSPOUTS (DS) AS SHOWN ON PLAN.
11. ALL BARGE RAFTERS TO BE 2 X 10' WITH A 1 X 3 BRICK MOLD UNO.
12. ALL RAFTER HANGERS SHALL BE OF SIMPSON L86U OR L15 TYPE, UNO.
13. PROVIDE (2) 6 1/2" IN. SCREENED ATTIC AIR VENTS AT RIDGE WITH 1/8" CORROSION RESISTANT SCREENED MEAT AND EQUALY SPACED AS SHOWN ON PLAN. PROVIDE (2) 6 1/2" IN. SCREENED ATTIC AIR VENTS AT EAVES WITH 1/8" CORROSION RESISTANT SCREENED MEAT AND EQUALY SPACED. A MINIMUM OF ONE (1) SQUARE FOOT OF VENTILATION AREA FOR EACH 160 SF. FT. OF ATTIC SPACE AREA REQUIRED. PROVIDE 50 PERCENT AT RIDGE AND 50 PERCENT AT EAVES. REFER TO ATTIC VENTILATION CALCULATION TABLE.
14. PROVIDE POSITIVE VENTILATION AT EACH END OF EACH RAFTER/BUS BAY AT VAULTED CEILING AREAS. INSTALL INSULATION Baffles AT EACH EAVE VENT BETWEEN BAYS. BAFFLES SHALL BE MADE RIGID, WEATHER RESISTANT MATERIAL AND MANTAIN 1" CLEAR AIR SPACE. VENTILATION IS ALSO REQUIRED AT BLOCKING LOCATIONS ABOVE PLATES.
15. ROOF DIAPHRAGM TO BE CONSTRUCTED WITH 16/32 EXPOSURE (C-D APA 240 RATED) Plywood OR 1" X 12" OSB, OR BETTER SHEATHING. LONG DIMENSION SHALL BE ON THE DIAPHRAGM AND EAVES. USE 16D COMMON NAILS TO SECURE SHEATHING WITH AD COMMON NAILS AT 6" O.C. AT GABLE ENDS AND ALL EDGES AND 8D COMMON NAILS AT 12" O.C. AT ALL INTERMEDIATE FRAMING MEMBERS.
16. DO NOT NOTCH, BORE OR DRILL THROUGH ANY SUPPORT COLUMNS, GIRDERS, BEAMS, JOIST SUPPORTING BEARING WALLS OR ANY OTHER CONCENTRATED LOAD BEARING MEMBER UNLESS SPECIFICALLY NOTED ON PLANS. CONTACT DESIGNER IF ANY QUESTIONS ARISE.
17. PROVIDE A SIMPSON H-23 HURRICANE CLIP AT EACH RAFTER CONNECTION TO EXTERIOR WALL TOP PLATES.
18. ATTICS WITH A CLEAR HEIGHT OF 30 INCHES OR MORE MUST BE PROVIDED WITH AN ACCESS. THE ACCESS OPENING SHALL 22" X 30" MINIMUM. OPENING TO HAVE 30" MINIMUM CLEARANCE FROM TOP OF OPENING TO BOTTOM OF ROOF ALL AROUND.
19. FLASHING SHALL BE INSTALLED AT JUNCTIONS OF CHIMNEYS AND ROOFS, IN ROOF VALLEYS AND AROUND ALL ROOF OPENINGS.
20. PROVIDE 4 X 4 OR (2) 2 X 4 LAMINATED WITH 16D + 12" O.C. KING POSTS (KP) WHERE SHOWN ON PLAN.
21. PROVIDE PURFLIN WALLS WHERE SHOWN ON ROOF PLAN. USE 2 X 4'S #24" O.C. AND/OR LINED-UP UNDER EACH RAFTER. EXTEND PURFLIN WALL DOWN TO BEARING MEMBER BELOW.
22. ALL RAFTERS TO BE NOTCHED (SEAT CUT) TO PROVIDE FULL BEARING AT SUPPORT MEMBERS.
23. ALL WINDOW HOPS TO BE 4 X 10, UNO.

ATTIC VENTILATION CALCULATIONS:

VENTILATION REQUIRED IN ATTIC AREA: 3498 SQ. FT. X 144 SQ. IN. - 1/160 = 3388 TOTAL SQ. IN. REQUIRED			
LOCATION	REQ. SQ. IN.	NO. OF VENTS	VENT SIZE: TOTAL SQ. IN.
AT RIDGE	1619	29	61 sq.in.
AT EAVES	1619	84	20 sq.in.
TOTAL:	3388	112	81 sq.in.

SYMBOLS LEGEND:

- (x) DENOTES (2) CRIPPLE STUDS (2X WIDTH OF WALL) UNO. 3-STUD ASSEMBLY MAY BE USED IN LIEU OF 4X4 POST. 4-STUD ASSEMBLY MAY BE USED IN LIEU OF 6X6 POST.
- (□) BEAM SCHEDULE CALLOUT.
- (---) BEARING WALL DETAIL.
- (SD) HOUSE WIRED SMOKE DETECTOR.
- (ea) FLOOR FRAMING DETAIL.
- (DS) DOWNSPOUT TO RAINDRAIN BELOW.
- (---) INDICATES ROOF FRAMED OVER ROOF FOLIO. USE 2X8 RAFTERS #24" O.C. ON HIPS AND RIDGES, 2X10 VALLEY RAFTERS LAID FLAT ON TRUSSES BELOW.
- (KP) 4X4 KING POST (KP) FROM HIP, VALLEY AND/OR RIDGE TO BEARING MEMBER BELOW. REFER TO DETAIL.
- (DI) DETAIL CALLOUT OVER SHEET *.
- (---) 4X10 HEADER (UNO).

SEE STRUC. ENGR. SHEETS

SEE TRUSS ENGR. SHEETS FROM MANUF.

**CONTRACTOR TO CONFIRM EXIST. CONDITIONS,
& INFORM DESIGNER OF ANY DISCREPANCIES, TYP.**


IMPORTANT DISCLOSURE
PLEASE READ:


THE PLANS YOU HAVE PURCHASED ARE FOR THE CONSTRUCTION OF ONE HOME ONLY.
IT IS ILLEGAL TO COPY THESE PLANS AND IT IS ILLEGAL TO BUILD FROM THESE PLANS MORE THAN ONCE WITHOUT THE WRITTEN PERMISSION OF THE DESIGNER.
THESE PLANS ARE COPYRIGHTED AND IT IS A VIOLATION OF FEDERAL COPYRIGHT LAW TO REPRODUCE THESE PLANS OR ANY PORTION THEREOF.
ANY VIOLATION OF ITS COPYRIGHTED DESIGNS AND PLANS, INCLUDING BUT NOT LIMITED TO THE ACT OF REPRODUCING THE PLANS, IS A CRIMINAL OFFENSE.
THE RESPONSIBILITY OF THE CONTRACTOR TO CONSTRUCT THE HOME DESCRIBED RESTS ON ANY PARTICULAR SITE AND IN ACCORDANCE WITH LOCAL CODES AND REGULATIONS.
FOWLER HOME DESIGN LLC TAKES NO RESPONSIBILITY FOR THE CONFORMANCE OF THIS PLAN TO ANY CODE OR ANY BUILDING CODE.

ROOF FRAMING PLAN

1/4"=1'-0"


**ALL ROOF SLOPES TO BE 8:12 U.N.O.
ALL EAVES TO BE 1'-0" U.N.O.**






CROSS SECTION A.

1/4"=1'-0"



CROSS SECTION B.

1/4"=1'-0"




STAIR DETAIL
SCALE: N.T.S.

SEE STRUC. ENGR. SHEETS

CONTRACTOR TO CONFIRM EXIST. CONDITIONS,
& INFORM DESIGNER OF ANY DISCREPANCIES, TYP.

IMPORTANT DISCLOSURE
- PLEASE READ:

THE PLANS YOU HAVE PURCHASED ARE FOR THE CONSTRUCTION ONE HOME ONLY. UNDER NO CIRCUMSTANCES IS IT LEGAL TO SELL PLANS FOR MORE THAN ONE HOME WITHOUT THE WRITTEN CONSENT FROM THE DESIGNER FOWLER HOME DESIGN LLC. IT IS A VIOLATION OF FEDERAL COPYRIGHT LAWS TO REPRODUCE THESE PLANS. FOWLER HOME DESIGN LLC WILL FULLY PROSECUTE ANYONE WHO REPRODUCES OR DISTRIBUTES THESE PLANS. FURTHERMORE, IT IS UNDERSTOOD THAT IT IS COMPLETELY THE RESPONSIBILITY OF THE CONTRACTOR TO DETERMINE THE HOME DESCRIBED HEREIN ON ANY PARTICULAR SITE AND WITHIN THE CONFINES OF THE GOVERNING JURISDICTION. FOWLER HOME DESIGN LLC MAKES NO WARRANTY AS TO THE CONFORMANCE OF THIS PLAN TO ANY CODE OR ANY BUILDING CODE.



CROSS SECTION C.

1/4"=1'-0"